

PESHAWAR DEVELOPMENT AUTHORITY

BOQ

Name of work:


Providing & Installation of Sub-Station and HT Line extension to Police station Zone -2 . Regi Model Town, Peshawar.

S.#	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
	Providing & installation of the following items, as per WAPDA's standard design and specifications.				
1	100 KVA 11/0.4 KV transformer	1	No	425,775.00	425,775.00
2	Stay Set Complete	2	No	2,423.00	4,846.00
3	Double pole platform	1	No	14,881.00	14,881.00
4	Nut & Bolt 10" 5/8"	14	No	111.00	1,554.00
5	Pin Insulator	20	No	842.00	16,840.00
6	Loop deadend clamp Wasp LC-16	6	No	172.00	1,032.00
7	Earthing of transformer with copper plate 2'x2'x1/8", copper wire, excavation 4'x4'x15', placing in mixture of salt and charcoal etc. (earthing material), 1/2" GI pipe of 16' length, backfilling.	1	NO	21,824.00	21,824.00
8	Stay Wire GSL 10mm	27	kg	167.00	4,509.00
9	P.G Connector T-110	9	No	149.00	1,341.00
10	Drop out cut outs (SY-II units)	3	No	8,171.00	24,513.00
11	Steel-X-Arm	6	No	4,814.00	28,884.00
12	Double Pole D fitting Complete	1	NO	3,214.00	3,214.00
13	Nut & Bolt 1-1/2" 5/8"	14	No	42.00	588.00
14	11 kv Disc Insulator	6	No	1,257.00	7,542.00
15	Eye Nut	6	No	114.00	684.00
16	Double Arm Bolts 12" 5/8	12	No	213.00	2,556.00
17	ACSR Rabbit conductor(7/.132)	3100	Mtr	75.00	232,500.00
18	Installation/Erection of PDA furnished HT PC Pole	5	No	2,328.00	11,640.00
19	Installation/Erection of PDA furnished LT PC Pole	1	No	2328	2,328.00
20	Three Phase energy meter (To be paid to PESCO as per demand note)	1	No	50000	50,000.00
Total amount Rs =					857,051.00


Assistant Director,
PDA, Hayatabad.

Contractor:

% Above Below:
In Figures _____.


Dy Director (E) PDA
Hayatabad.