

Peshawar Development Authority, Peshawar

Major head: Maintenance of Street Lights at Regi Model Town.

Sub head: - Purchase of Accessories for Maintenance Of Street Lights at Regi Model Town Peshawar.

BOQ

S.No	Description	Qty	Unit	Rate	Amount
1 NSR	Providing & safe handling of 70 watt Son-T lamps (Phillips or Equivalent),	200	Each	813	162600.00
2 NSR	Providing & safe handling of 70 watt sodium Ballast (Phillips or equivalent)	200	Each	1840	368000.00
3 NSR	Providing & safe handling of screw type holder E27	100	Each	84	8400.00
4 NSR	Providing & safe handling of screw type holder E40	100	Each	179	17900.00
5 NSR	Providing & safe handling of 250 watt Son-T lamps (Phillips or Equivalent)	100	Each	1135	113500.00
6 NSR	Providing & safe handling of 250 watt sodium Ballast (Phillips or equivalent)	100	Each	4063	406300.00
7 NSR	Providing & safe handling of igniter SN-58 for 70/250 watt sodium lamp (Phillips or Equivalent)	300	Each	502	150600.00
8 15-05-c	Supply of single core PVC insulated copper conductor 250/440 V Grade cable: 7/0.029	630	Meter	53.37	33623
9 15-08-c	Supply of twin core PVC insulated sheathed copper conductor 250/440 V Grade cable:7/0.029	630	Meter	99.82	62886.6

10 15-05-e	Supply of single core PVC insulated copper conductor 250/440 V Grade cable:7/0.044	180	Meter	131.60	23688.00
11 15-70-c	Supply & Erection transpower auto circuit breaker 3-phase,400V fungus moisture proofing:100Amp.	45	Each	5002	225090
12 15-05-a	Supply of single core PVC insulated copper conductor 250/440 V Grade cable:3/0.029	540	Meter	25.35	13689
13 15-71-d	Supply and safe handling of single phase auto imported circuit breaker 30 Amp.	200	Each	512.40	102480.00
14 NSR	Providing & safe handling of twin core 7/.052 PVC insulated aluminum cable	1000	Meter	93	93000.00
15 NSR	Providing & safe handling of TP magnetic contactor for 100A,MC-100A,4-10x	30	Each	15697	470910.00
16 NSR	Providing & safe handling of timer TB-38809K 220-240VAC Quartz Type with 500 Hours Power failure backup.	15	Each	12967	194505.00
17 NSR	Providing & safe handling of cut out Grip 60 Amp.	150	Each	114	17100.00
18 NSR	Supply of insulation tape.	352	Each	30	10560.00
Total Rs.					2474833/-

Shahzad

Assistant Director, (E/RMT),
PDA, Hayatabad.

Contractor:

% Above Below:

In Figures _____.

[Signature]

DEPUTY DIRECTOR (ELECTRICAL),
PDA, HAYATABAD, PESHAWAR