

**PESHAWAR DEVELOPMENT AUTHORITY**


NAME OF WORK: EXTERNAL ELECTRIFICATION OF RMT, PESHAWAR.

Sub Head: PROVIDING OF ALLIED MATERIAL FOR 100 KVA & 200 KVA TRANSFORMERS & L.T LINE FOR ZONE,  
III & IV, RMT, PESHAWAR.

**BOQ**


supply of the following items as per Wapda's standard Design and Specifications					
S.No	Description	Qty	Unit	Rate	Amount
1	supplying of stay Set complete.	100	Nos	2293	229300
2	supplying of double pole platform complete.	40	Nos	13926	557040
3	supplying of nut & bolt 10" 5/8".	2000	Nos	103	206000
4	supplying of Pin Insulator - Pin for insulator.	160	Nos	790	126400
5	supplying of loop deadend clamp WASP LC 16.	400	Nos	156	62400
6	supplying of loop deadend clamp ANT LC 16.	400	Nos	163	65200
7	supplying of stay wire GSI 10mm.	8000	Kg	158	1264000
8	supplying of P.G connector T-110.	200	Nos	144	28800
9	supplying of dropout cutout (SY-II) Unit complete set.	40	Set's	7731	309240
10	supplying of steel X-Arm.	40	Nos	4525	181000
11	supplying of Definite.	40	Nos	3037	121480
12	supplying of nut bolts 1 1/2" 5/8" & of different types.	300	Nos	40	12000
13	supplying of nut & bolt 12" 5/8".	4000	Nos	113	452000
14	Earthing material copper plate, GI pipe, copper wire, copper Bolt	40	Nos	17646	705840
15	supplying of P.G connector T-150.	400	Nos	186	74400
16	supplying of D-Shackle along with spool insulator & cotter pin	5000	Nos	205	1025000
17	supplying of L.T structure pole 30ft.	40	Nos	23415	936600
				Total Rs:	6356700
				Total Rs:	6.357 millions

Contractor:

  
Assistant Director, (E/RMT),  
PDA, Hayatabad.

% Above Below:

In Figures \_\_\_\_\_.

  
Dy Director (E-II),  
PDA Hayatabad.