

PESHAWAR DEVELOPMENT AUTHORITY PESHAWAR.


(BILL OF QUANTITY)

Major Head :- MAINTENANCE OF WATER SUPPLY AND SEWERAGE HAYATABAD

Sub Head :- CONSTRUCTION OF DRAIN AT SECTOR D-5, PHASE-I HAYATABAD.

S/No	MRS Code	Description	Qty:	Unit	Rate	Amount
1	03-08-b	Earth excavation in open cut 1.5m-3m depth for S.W Drains etc & disposal in hard soil.	283.70	M3	224.47	63682.139
2	06.-05-i	Plain cement concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	56.74	M3	5481.08	310996.479
3	07-04-a-03	Pacca brick work in foundation and plinth in cement, sand mortar 1:4	158.06	M3	8052.81	1272827.148
4	06-05-f	Plain cement concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	12.16	M3	7257.86	88255.577
5	11-09-b	Cement plaster 1:4 upto 20' height ½" thick	691.68	M2	217.80	150647.904
6	03-60-c	Structural backfill using common material available at site.	162.13	M3	442.27	71705.235

Total Rs. 19,58,114/-




Assistant Director (Sanitation)
PDA Hayatabad

Contractor's rate At Par/ Above/Below

1. In Figures _____

2. In Words _____

Contractor



Deputy Director (Sanitation)
PDA Hayatabad