


PESHAWAR DEVELOPMENT AUTHORITY PESHAWAR.

(BILL OF QUANTITY)

Name of work:- **CONSTRUCTION OF SOLID WASTE CHAMBER IN MARKETS AND PAVEMENT OF ROAD SHOULDER WITHIN HAYATABAD TOWNSHIP PESHAWAR**

S/No	MRS 2017	Description	Qty:	Unit	Rate	Amount
1	06.05-i	Plain cement concrete including placing, compacting, finishing & curing Ratio (1:4:8)	10.41	M3	5481.08	57058.04
2	06.05-f	Plain cement concrete including placing, compacting, finishing & curing Ratio (1:2:4)	26.25	M3	7257.86	190518.83
3	07.07-a-03	Pacca brick work other than building upto 10 feet height cement, sand mortar 1:4	26.55	M3	8444.27	224195.37
4	11.09-b	Cement plaster 1:4 ½" thick	116	M2	217.8	25264.80

Total Rs. 4,97,037/-


Assistant Director (Sanitation)
PDA Hayatabad

Contractor's rate At Par/ Above/Below

1. In Figures _____

2. In Words _____

Contractor


Deputy Director (Sanitation)
PDA Hayatabad